BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

SCHEDULE-B

Name Of Work : Providing Assured Minimum facilities (AMF) to all Polling Stations of Loksabha Elections -2019 pertains to ward No 15

SLNo	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	Suppying Dmiking water through 20 liters cans to polling stations (Total No of polling stations 37Nos) 5 cans / booth x 2days=10 Nos	Each	580	50.00	
2	Supplying water to toilets and bath rooms (Water Tankers) for three Govt schools	Each	6	500.00	
3	Supplying Furnitures to polling stations, 2x6 tables size = 4 tables each boothx 2days=8 Nos.	Each	464	50.00	
4	Chairs 10 Nos per boothx 2days	Each	1160	10.00	
5	tables 2.5x2.5 tables for voting machine (1 Nos for 2 days)	Each	116	90.00	
6	Suppying Buckets to polling stations	Each	52	150.00	
7	Supyling mugs to polling stations	Each	52	50.00	
8	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - Ramps to Govt schools	Cum	2.2	5000.00	
9	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications - Ramps	Cum	0.49	5000.00	
10	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. size of gate 2.4mx1.4m	Sqm	5.04	700.00	
11	Providing shamiyana to polling stations (20x40 = 800 Sqft for 2days/14.00 per Sqft)	Sqft	3200	13.00	

Scanned by CamScanner